

 **BID SCHEDULE**

This Contract is a UNIT PRICE CONTRACT, and BIDDER shall include all costs BIDDER may anticipate to complete the work during the length of this project and the contract. Each BIDDER shall include all extras the BIDDER may determine necessary to provide the quantity of WORK required by the Contract Documents. Fill in the bid amount for each category and total base bid below and on the following sheets.

The BASIS OF AWARD shall be the lowest responsive / responsible bidder based on the total of the following four (4) scopes:

1. 10th Avenue Roadway Base Bid
2. 10th Avenue Utility Bid
3. Cypress Street Base Bid
4. Cypress Street Utility Bid

**SCOPE 1 - 10th Avenue Roadway Base Bid**

Item No.	Description	Quantity	Unit	Cost / Unit	Total Cost
102-1	Maintenance of Traffic	1	LS	\$	\$
101-1	Mobilization	1	LS	\$	\$
104-10-3	Sediment Barrier - Staked Silt Fence	250	LF	\$	\$
110-1-1	Clearing and Grubbing - Removal of Base / Sub Base / Asphalt / Curbing / Storm Inlets and Drainage Pipes	1	LS	\$	\$
160-4	Type 'B' Stabilization - (8" Deep)	126	SY	\$	\$
160-4	Type 'B' Stabilization - (12" Deep)	7170	SY	\$	\$
285-7-04	Optional Base - Base Group 4 (6" Deep)	404	SY	\$	\$
285-7-06	Optional Base - Base Group 6 (8" Deep)	7458	SY	\$	\$
327-70-1	Mill Existing Asphalt Pavement - 1" Avg. Depth	246	SY	\$	\$
W-1	1 1/2" Type S-1 Asphalt w/Prime/Tack Coat (First Course)	592	TN	\$	\$
W-2	1" Type S-3 Asphalt w/Tack Coat (Surface Course)	428	TN	\$	\$
425-1-521	Inlet, Type C DBI	3	EA	\$	\$
425-1-541	Inlet, Type D DBI	1	EA	\$	\$
430-175-112	Pipe Culvert Optional Material - 12" RCP	65	LF	\$	\$
430-175-215	Pipe Culvert Optional Material - 12"X18" ERCP	111	LF	\$	\$
430-175-218	Pipe Culvert Optional Material - 14"x23" ERCP	131	LF	\$	\$
430-982-121	Mitered End Section - 12" RCP	2	EA	\$	\$
430-982-123	Mitered End Section - 12"X18" ERCP	2	EA	\$	\$
430-982-125	Mitered End Section - 14"X23" ERCP	6	EA	\$	\$
430-984-125	Mitered End Section - 18" RCP	1	EA	\$	\$
520-1-10	Concrete Curb & Gutter, Type F	319	LF	\$	\$
522-1	Concrete Sidewalk, 4" Thick	230	SY	\$	\$
522-2	Concrete Sidewalk & Driveway, 6" Thick	103	SY	\$	\$
570-1-2	Performance Turf - Sod	3450	SY	\$	\$
700-1-11	Single Post Sign, Furnish and Install, Ground	19	AS	\$	\$
706-3	Retro-Reflective Pavement Markers (Blue)	4	EA	\$	\$
710-11-123	Painted Pavt Mark, Standard, White, Solid, 12"	472	LF	\$	\$
710-11-125	Painted Pavt Mark, Standard, White, Solid, 24"	200	LF	\$	\$
711-11-123	Thermoplastic, Standard, White, Solid, 12"	472	LF	\$	\$
711-11-125	Thermoplastic, Standard, White, Solid, 24"	200	LF	\$	\$
711-11-180	Thermoplastic, Standard, White, Solid, Yield	19	LF	\$	\$
711-15-101	Thermoplastic, Standard, White, Solid, 6"	184	LF	\$	\$
711-15-201	Thermoplastic, Standard, Yellow, Solid, 6"	200	LF	\$	\$

Subtotal 1 - Scope 1 - 10th Avenue Roadway Base Bid

\$ \_\_\_\_\_

Subtotal 1 - Scope 1 - 10th Avenue Roadway Base Bid (Written in Words)

*\* Available AS excel worksheet with Tabs on Demandstar OR Contact DA-hene Davis 863-494-4114 ext 363 ddavis@arcadius-fl.gov*